III. அளவு அளவையியிடுதல் – விரிவான மதிப்பீடு மற்றும் சுருக்க மதிப்பீடு (Quantity Surveying – Detailed and Abstract Estimate)

7 ஓர் சுற்றுச் சுவருக்கான விரிவான மதிப்பீடு மற்றும் சுருக்க மதிப்பீடு கீழ்கண்ட பணிகளுக்கு தயார் செய்தல்
(Prepare the detailed and abstract estimate for a Compound wall for the following items of work.

1. Earth work excavation for foundation
2. Foundation concrete in P.C.C 1:4:8
3. R.C.C Footing in 1:1.5:3 mix
4. R.C.C columns in 1:1.5:3 mix
   a. Up to Grade beam
   b. above Grade beam
5. R.C.C Grade beam 0.23×0.30 m size in 1:1.5:3 mix
6. Brick work above the Grade beam in C.M 1:5 mix
7. Plastering the Brick work (Both sides)
8. White washing for the plastered wall (Both sides)
9. Providing and fixing of Gate.
10. Painting with enamel paint for the gate.

Detailed Estimate:

Sl. No.	Description of Item	Nos.	Dimensions in Metre			Quantity	Total
			Length	Breadth	Depth/Height		

Abstract Estimate:

Sl. No.	Description of Item	Quantity	Rate/Unit	Amount

BCE_Practical.indd 242 12/12/2019 5:54:25 PM